

**Trail Hardening
Hoosier National Forest
LRT: FY22**

LRT: Priority Watershed Improvement; Youngs Creek Trail Hardening, Youngs Creek Trail 202.10

	Title	Description	Estimated Quantity	Unit	Unit Price	Total Price
Base Items						
	Aggregate Placement	Provide and place aggregate along trail from staging area through project area: trail segment length of 0.6 miles (3168'.) Aggregate to be placed at a width of 60" and a depth of 6" or as directed by COR, crowned where tread is level or outsloped to match existing tread where not level. Aggregate must be equipment compacted.				
	Mobilization	Costs associated with moving equipment to project area. Including weed wash/equipment cleaning of all equipment brought near and on the project area.				
	Geotech Fabric	Provide and place Geotech fabric at 5' width before placing aggregate in soft spots, mud holes, or other trouble areas. These will be staked by COR or otherwise directed at the start of the project.				

Grand Total:

The work sites can be accessed from various Orange County roads, particularly W County Road 550/560S. Staging areas for temporary gravel placement will be marked, or directed by COR. Access routes to work areas will be featured on project maps or directed by the C.O.R.