

**STATEMENT OF WORK
TO
INSTALL CAMERA EQUIPMENT**

1.0 INTRODUCTION

1.1 Organization

1.1.1 Identification. Utah Air National Guard, 151 Security Forces Squadron, 765 North 2200 West, Salt Lake City, Utah 84116-2999

2.0 TECHNICAL REQUIREMENTS

2.1 Scope of Work. This Statement of Work (SOW) identifies the work that shall be performed by the contractor for the installation of the purchased camera equipment. The contractor will be drilling small holes in the buildings to install the mounts for each camera and running CAT6 cabling through existing pathways.

2.2 Locations: Cameras to be installed includes the following locations:

2.2.1 180 deg camera for T Hallway and bldg 210, Bldg 45, and bldg 7 – Qty 4

2.2.2 Clearing Barrel Camera – Qty 1

2.2.3 Common Area – Qty 1

2.2.4 Hanger 3 & Bldg 220 – Qty 4

2.3 Installation:

2.3.1 Lift/ Ethernet Extenders -Camera Installation/Man Lift (if needed) for cameras at hanger 3 & bldg 220

2.3.2 Task 1 – The contractor shall perform labor and run cabling to replace 4 existing CAT5/CAT6 Cables from Bldg 200 to the main gate camera pole

2.3.3 Task 2 – The contractor shall perform labor and run new cabling to mount the cameras to in upstairs hallway of Bldg. 210, at Security Forces clearing barrel on the southwest corner of Bldg. 210 in and on hanger 3 and Bldg. 220.

2.3.4 Task 3- The contractor will be installing the new server in the hallway in building #210, a new fiber switch in the communications switch room. They will also be installing switches in building #7 and building #220.

2.3.5 Task 4– The contractor will be installing 3 new TVs in building #401 with TV mounts.

3.0 INSPECTION AND ACCEPTANCE

3.1 The finished product will be inspected by the Contractor and Functional Area Chief